WORK	TIME	MATERIAL	SIZE	QUANTITY	PRISE PER PIECE	TOTAL PRICE	
Riving	10	------	-----	-----	-----	-----	
Montering karkas	4	wood lekte	48x48x3200	14	75	~1250	
---//---	---//---	skrue	50x 2 TRX 25	400	150 kr. pack 150 skrue	~600	
Ceiling lekte montering	4	---//---	---//---	---//---	---//---	-----	
Isolation	4	Glava-isola	50x570	20 m²	50 kr/ m²	~1000	
kabel montering	8	Kabal + gofra	1,5 mm	30 m	2500	~2500	
Ror (pipe) montering	10	water pipe (PEX)	2.5x15x25000 mm	50 m	700	~1500	
water sluk montering	3	Drinerr. sluke	110mm	1	359	~400	
Drinerring sis montering	7	water pipes	90x 3000	4	800 per 3 m pipe	~3200	
---//---	---//---	water pipe vinkel	90x 90°	6	100	~600	
---//---	---//---	water pipe	50x 3000	1	400 per 3m pipe	~400	
Toilet sis montering	8	Geberit wc aisiern	230x 600x 1400	1	3500	~4000	
dampsperre montering	1	dampsperre (NBVI)	0.2x 2700	1x 40 m²	350	~400	
Ceiling gips montering	3	wotrums gips	12x 900x 2700	8 m²	150 kr. m²	~1200	
Ceiling sparkle	2	Sparkle masse	3 kg	1	200	~300	
Ceiling maling	2	Farge (white)	3 kg	1	350	~400	
Montering USB plate	5	USB plate	12x1200x2400	20 m²	55 kr. m²	~1500	
Drinar. ror (pipe) monter.	5	dren. pipe	70 mm	6 m	150	~600	
Wotrums plate	5	wotrums plate	10x600x2400	25	185	~4500	
---//---	---//---	skrue	35mm	2 pack	250 kr. pack 100 skue	~ 500	
wotrums smore membran	5	smore membran	35 m² - 23 kg	1 bags	1150	~ 1150	
vitrom vinkel membran	2	wotrums vinkel	100x100x100	12	50	~ 600	
Floor grundering	1	tiff grundering	1 l	1	150	~150	
Floor belong+ armering	4	B 30 of B 40 class	25 kg	8	75	~550	
Montering warme kabel	10	Warme kabel	100 w 4.1 m² - 410w	1	2900	~3000	
Avreting masse on floor	3	avreting masse	20 kg	4	80	~350	
Fliss montering (wall)	20	fliss	600x600	30 m²	MUST CHOICE	WITCH FLISS	PRICE OF THIS PART
fliss montering floor	6	fliss	600x600	9 m²	---//---	---//---	
fliss Fugging	4	fuggemass	5 kg	40 m²	---//---	WITHC COLOUR	WE FIGURED WHEN
shower doors + shower	2	Glass dor+shower	900x 900x 2100	1	MUST CHOICE	WITC TIPE	
furniture montering	4	Skaphandbeslutrdan	400x 600x 900	1	---//---	---//---	YOU DECIDE OF TIPE
Drinar montering	1	drinrar	600x 900	1	---//---	---//---	
Silicone + acrylic	4	silicone	Same colour fug	5 tube	150	~600	
Connect electric+water	3	spotlight+switch	-----	4+1	200	1000	
Make celling stears	5	using old one	-----	-----	-----	-----	
Extra position	5	------	------	-----	-----	-----	
Totally results	~160				~35750	MIDDLE PIECE FROM SHOP	
	~35750 + fliss + furniture = ???				+ FURNITURE AND FLISS COSTS		
PRICE OF DELIVERY	6000						
PRICE OF WORK	55000						
TOTAL COST	~ 96750						